

EQUIPMENT NOTES

1. ITEMS #4 AND #128 IS EQUIVALENT TO 96 LN FT OF SHELVING.
 2. G.C. TO SEAL ALL COUNTER PENETRATIONS.
 3. INSTALL ALL SALES AREA COUNTERS ON TOP OF TILE.
 4. WINDOW SHADES TO BE ATTACHED TO TOP OF THE WINDOW SILL.
 5. G.C. TO PROVIDE FLEXIBLE LIGHT BLOCKING MATERIAL AROUND THE FROSTER SHROUD.
 6. G.C. TO PROVIDE SEPARATE 1" PVC DRAIN FROM ICE MAKER UNIT TO FLOOR SINK.
 7. G.C. TO PROVIDE SEPARATE 1 1/2" PVC DRAIN FROM FOUNTAIN TO FLOOR SINK.
 8. SYRUP LINES FROM BIB RACKS TO FROSTERS AND FOUNTAIN MACHINES TO BE ROUTED DIRECTLY THROUGH WALL MOUNTED ABOVE THE COUNTERTOP.
 9. PROVIDE HOMERUN CONDUITS AS FOLLOWS:
 - a) FRAME RACK TO BACK OFFICE
 - c) FRAME RACK TO ATM
 - c) FRAME RACK TO POS – SALES COUNTER
 - d) BACK OFFICE TO POS – SALES COUNTER (ACCOMMODATE SECURITY INTERFACE AS WELL)
- SEE SLAB PENETRATION PLAN SHEET A2.0 FOR MORE INFORMATION
10. SEE MECHANICAL, PLUMBING AND ELECTRICAL DRAWINGS FOR ADDITIONAL INFORMATION REGARDING EQUIPMENT ON THIS SCHEDULE.
 11. G.C. TO PROVIDE FULL HEIGHT S/S CORNER GUARDS AT TRAFFIC AREAS.

GreenbergFarrow

1430 W. Peachtree St., Suite 200
Atlanta, GA 30309
t: 404 601 4000 f: 404 601 3980

COPYRIGHT NOTICE

This drawing is the property of the above referenced Professional and is not to be used for any purpose other than the specific project and site named herein, and cannot be reproduced in any manner without the express written permission from the Professional.

ISSUE/REVISION RECORD

DATE	DESCRIPTION
01/19/15	PERMIT SET

PROFESSIONAL SEAL

PROFESSIONAL IN CHARGE
HUGHES THOMPSON

PROJECT MANAGER
OSCAR FLORES

QUALITY CONTROL
WARREN DRURY


DRAWN BY
ARMANDO MATA

PROJECT NAME

**CIRCLE K
STORES, INC.**

COLORADO SPRINGS
COLORADO

E. FOUNTAIN BLVD & ACADEMY PARK LOOP



CIRCLE K STORES INC.

PROJECT NUMBER
20130780

SHEET TITLE

**EQUIPMENT
SCHEDULE
FLOOR PLAN
W/O BEER CAVE**

SHEET NUMBER

A7.1-CS

A1

EQUIPMENT SCHEDULE FLOOR PLAN AND CABINETRY PLAN (WITHOUT BEER CAVE)

NTS.