SAN JUAN COUNTY.

FLOOD INSURANCE RATE MAP

(N.T.S.)

SHEET INDEX:

COVER SHEET C-0.0

SITE PLAN C-1.0

C-1.1 **DEMOLITION PLAN**

PAVING PLAN C-2.0

C-3.0GRADING PLAN

C-4.0DRAINAGE PLAN

C-5.0EROSION CONTROL PLAN PHASE I

C-5.1 EROSION CONTROL PLAN PHASE II

C-5.2EROSION CONTROL DETAILS

C-6.0UTILITY PLAN

C-7.1DETAIL SHEET

C-7.0DETAIL SHEET

C-7.2DETAIL SHEET

SURVEYOR

ALTA/ACSM LAND TITLE SURVEY

RED PLAINS SURVEYING CO. 6744 MELROSE LANE OKLAHOMA CITY, OK 73127 (405) 603-7842

SURVEYOR'S PROJECT NO. M11469A

GEOTECHNICAL ENGINEER:

TERRACON CONSULTANTS, INC.

#4A CR 3499 FLORA VISTA, NM 87415 (505) 334-2900 PROJECT NO. 69135013

SITE DEVELOPMENT PLAN



819 NM 516 FLORA VISTA SAN JUAN COUNTY, NEW MEXICO

OWNER/DEVELOPER:


CIRCLE K STORES INC.


CONTACT: SHELLY HUFF

1199 S. BELTLINE RD. STE 160 COPPELL, TEXAS 75019 (972) 537-5938

ENGINEER:

CONTACT: MARLEY PHILLIPS 5500 DEMOCRACY DR. SUITE 125 PLANO, TEXAS 75024 (972) 514-7641





CONTACTS:

PHONE: (505) 333-3129

SAN JUAN COUNTY 100 S. OLIVER DR. AZTEC, NM 87410

<u>WATER</u>

FLORA VISTA WATER 2c CR 3499 FLORA VISTA, NM 87415 CONTACT: RICK MITCHELL PHONE: (505) 334-6045

<u>ELECTRIC</u>

FARMINGTON ELECTRIC UTILITY SYSTEM 101 N. BROWNING PKWY. FARMINGTON, NM 87401 CONTACT: JONETTE MANSKER PHONE: (505) 599-8312

<u>TELEPHONE</u>

CONTACT: KEN DOUGLAS

PUBLIC WORKS (ROADWAY DEPT.)

CONTACT: TJ RICHARDS PHONE: (505) 334-4574

CENTURY LINK PHONE: (800) 244-1111

CONTACT: DOUG HATFIELD PHONE: (505) 334-1180

<u>NMDOT</u>

NMDOT DISTRICT 5 7315 CERRILLOS RD. SANTA FE, NM 87502 CONTACT: JAVIER MARTINEZ PHONE: (505) 995-7800

WASTEWATER


NM ENVIRONMENT DEPT. FARMINGTON FIELD OFFICE 3400 E. MESSINA DR. STE 5000 FARMINGTON, NM 87402 CONTACT: SHERMAN S. PARANANDI PHONE: (505) 566-9754


NEW MEXICO GAS COMPANY 603 W. ELM ST. FARMINGTON, NM 87401 PHONE: (888) 664-2726

2	08-07-14	DEVELOPMENT PLANS	NN
1	05-19-14	INITIAL BIDSET	KK
NO.	DATE	DESCRIPTION	BY

JOB NO. 20130768

DATE: 08-07-14





EXISTING LEGEND:

S THE OFF S TRAFFIC	LIST OF
O-PIPELINE VENT P-TELE. PED. CONTROL BOX	<u>ABBREVIATIONS</u> U/G – UNDERGROUND
CAS METER ED -FLEC PEDESTAL	HC — HANDICAPPED CONC. — CONCRETE
-SIGNAL LIGHT -WATER VALVE -GROUND LIGHT	RET. — RETAINING APPROX. — APPROXIMATE SAN. — SANITARY
A -PIPELINE MRKR Ø -POWER POLE -UTILITY POLE	ASPH. — ASPHALT TYP. — TYPICAL
-MAIL BOX -PULL BOX -GAS VALVE	BLDG. — BUILDING PED. — PEDESTAL PLTR. — PLANTER
→ BUSH → FIRE HYDRANT → TEL. U.G. MRKR.	G/R — GAS REGULATOR G/L — GROUND LIGHT
T - CURB INLET -TREE E-ELEC. MANHOLE	TRANS — TRANSFORMER F.F. — FINISHED FLOOR
SS -SAN. SEW. M.H. S -STM. SEW. M.H.	C - CENTER LINE R.O.W - RIGHT-OF-WAY
GP-GUARD POST -BARB WIRE FCE	FCE. — FENCE BIA. — DIAMETER
□ - TV PED -CLEAN OUT	BLVD. — BOULEVARD B/L — BUILDING SETBACK LINE
— FLAG POLE — MONITOR WELL TO	ESMT. — EASEMENT A/S — AUTO-SPRINKLER
☐ - ELEC TRANS ——STS—— ☐ - TRASH CAN STORM SEWER ——SS——	DIST. — DISTANCE BRNG. — BEARING
-F/O-T UNDERGROUND SANITARY SEWER FIBER OPTIC COMMUNICATION WATER LINE	W/UGS — WITH UNDERGROUND SERVICE
UTA	MW — MONITOR WELL STAT. — STATUTORY M — MEASURED
-CONCRETE WHITE HYDRANT IN IRON GRATE	DIMENSION P — PLAT DIMENSION IG — IRON GRATE
-TRAFFIC DIRECTION	R - RECORD DIMENSION RD - ROOF DRAIN
TR - TOP OF RIM FL - FLOW LINE	P.O.M. — POINT OF MEASUREMENT

SITE KEY NOTES

- S1 CONCRETE CURB & GUTTER
- S3 TAPER CURB TO MATCH EXISTING.
- S4 TAPER CURB FROM 6" TO 0" OVER 2'. S5A LIMITS OF SAWCUT AND PAVEMENT REMOVAL.

PROPERTY LINE

PROPOSED CURB & GUTTER

COLUMNS AND BOLLARDS

GRADING/DRAINAGE PLANS)

PROPOSED PARKING SPACES

PROPOSED STAMPED BRICK CONCRETE

MULTIPLE PRODUCT DISPENSER WITH CANOPY

PROPOSED SITE LIGHT, SEE PHOTOMETRIC

PROPOSED DRAINAGE STRUCTURES (SEE

- S5B MATCH EXISTING PAVEMENT/SIDEWALK ELEVATION.
- S6 STANDARD DUTY CONCRETE PAVING (PER PAVING DETAIL)
- S7 HEAVY DUTY CONCRETE PAVING (PER PAVING DETAIL)
- S8A CONCRETE SIDEWALK
- S8B PEDESTRIAN PATH PER CITY STANDARD
- S10 SIDEWALK RAMP @ 8.33% MAX.
- S11 DETECTABLE WARNINGS PER ADA REQUIREMENTS S14 PYLON SIGN (SEPARATE PERMIT)
- S16 ADA ACCESSIBLE PARKING SPACE STRIPING & SYMBOL OF
- ACCESSIBILITY (TYPICAL-PER ADA AND LOCAL REQUIREMENTS)
- REQUIREMENTS)
- S18 VAN ACCESSIBLE PARKING SIGN (TYPICAL-PER ADA AND LOCAL REQUIREMENTS)
- S22 FIRE LANE STRIPING
- S23 PARKING STALL STRIPING (PER LOCAL CODES)
- S26A PEDESTRIAN CROSSWALK STRIPING
- S27 FIRE HYDRANT
- S29 TRANSFORMER PAD LOCATION (SEE UTILITY PLAN)
- S30 BOLLARD (SEE NOTE FOR NUMBER)
- S30A "INVERTED U" BOLLARD PER ARCH. PLAN (SEE NOTE FOR
- S31 LIGHT POLE (TYPICAL—PER LIGHTING PLAN)
- S32 LANDSCAPE AREA (PER LANDSCAPE PLAN)
- S33 LANDSCAPE ISLAND (PER LANDSCAPE PLAN) S35 "DO NOT ENTER" SIGN
- S40 EXISTING PAVEMENT TO REMAIN.
- S41 THICKENED EDGE OF PAVING.
- S42 MATCH EXISTING CONCRETE ISLAND (PER NMDOT
- REQUIREMENT)
- S46 RETAINING WALL WITH 4' FENCE PER PAVESTONE OR EQUAL
- S80 "INVERTED U" BIKE RACK (PER ARCH. PLANS)
- S81 UST VENT STACK, REFER TO FUELING PLANS
- S83 UNDERGROUND STORAGE TANKS, SEE FUELING PLANS FOR
- S85 CANOPY COLUMN
- S86 CURB INLET
- S90 CANOPY SIGN (PER ARCH. PLANS)
- S91 2' CONCRETE RIBBON

GENERAL SITE NOTES:

BEGINNING CONSTRUCTION.

BEGINNING EACH PHASE OF CONSTRUCTION.

- 1. CONTRACTOR MUST SECURE ALL NECESSARY PERMITS PRIOR TO STARTING WORK.
- 2. IF THE CONTRACTOR, IN THE COURSE OF THE WORK, FINDS ANY DISCREPANCIES BETWEEN THE PLANS AND THE PHYSICAL CONDITIONS OF THE LOCALITY, OR ANY ERRORS OR OMISSIONS IN THE PLANS OR IN THE LAYOUT AS GIVEN BY THE ENGINEER, IT SHALL BE HIS DUTY TO IMMEDIATELY INFORM THE ENGINEER, IN WRITING, AND THE ENGINEER WILL PROMPTLY VERIFY THE SAME. ANY WORK DONE AFTER SUCH A
- 3. CONTRACTOR SHALL BE RESPONSIBLE FOR VERIFICATION OF ALL SETBACKS, EASEMENTS, AND DIMENSIONS SHOWN HEREON BEFORE

DISCOVERY, UNTIL AUTHORIZED, WILL BE AT THE CONTRACTOR'S RISK.

- 4. ALL CONSTRUCTION MATERIALS AND WORKMANSHIP SHALL BE IN ACCORDANCE TO THE STATE AND LOCAL GOVERNMENT AGENCY LATEST CONSTRUCTION SPECIFICATIONS AND DETAILS.
- 5. ALL HANDICAP SITE FEATURES SHALL BE CONSTRUCTED TO MEET ALL FEDERAL, STATE AND LOCAL CODE.
- 6. NOTIFY THE CITY INSPECTOR TWENTY-FOUR (24) HOURS BEFORE
- 7. THE CONTRACTOR SHALL CAREFULLY PRESERVE BENCHMARKS, REFERENCE POINTS, AND STAKES.
- 8. ARCHITECTURAL PLANS ARE TO BE USED FOR BUILDING STAKE OUT.
- 9. ALL DIMENSIONS ARE FROM FACE OF BUILDING, CURB, AND WALL UNLESS OTHERWISE SPECIFIED ON PLANS.
- 10. CONTRACTOR SHALL MAINTAIN THE SITE IN A MANNER SO THAT WORKMEN AND PUBLIC SHALL BE PROTECTED FROM INJURY, AND ADJOINING PROPERTY PROTECTED FROM DAMAGE.
- 11. CONTRACTOR IS RESPONSIBLE FOR DAMAGE TO ANY EXISTING ITEM AND/OR MATERIAL INSIDE OR OUTSIDE CONTRACT LIMITS DUE TO CONSTRUCTION OPERATION.
- 12. ALL STREET SURFACES, DRIVEWAYS, CULVERTS, CURB AND GUTTERS, ROADSIDE DRAINAGE DITCHES AND OTHER STRUCTURES THAT ARE DISTURBED OR DAMAGED IN ANY MANNER AS A RESULT OF CONSTRUCTION SHALL BE REPLACED OR REPAIRED IN ACCORDANCE WITH THE SPECIFICATIONS.
- 13. ALL ROAD WORK SHALL BE PERFORMED IN ACCORDANCE WITH THE STATE AND LOCAL GOVERNMENT AGENCY SPECIFICATIONS.
- 14. STANDARD/HEAVY DUTY PAVEMENT AND CONCRETE SECTIONS SHALL FOLLOW THE RÉCOMMENDATIONS OF THE GEOTECHNICAL REPORT PREPARED BY TERRACON CONSULTANTS, INC., DATED JAN 31, 2014. SEE CIVIL DETAILS.
- 15. ALL CURB RADII SHALL BE 5' UNLESS OTHERWISE NOTED ON THE

GreenbergFarrow

5500 Democracy Dr. Suite 125 Plano, TX 75024

t: 972 514 7641

PROJECT TEAM

be reproduced in any manner without the **ISSUE/REVISION RECORD** DESCRIPTION 08-07-14 DEVELOPMENT PLAN

This drawing is the property of the above

referenced Professional and is not to be used

for any purpose other than the specific project and site named herein, and cannot

PROFESSIONAL IN CHARGE CIVIL PROF IN CHARGE PROFESSIONAL ENGINEER LICENSE NO. 21307 PROJECT MANAGER

MARLEY PHILLIPS **QUALITY CONTROL** KIEW KAM, PE DRAWN BY NICOLE NOVACK

PROJECT NAME


SAN JUAN COUNTY


NEW MEXICO 819 NM 516 **FLORA VISTA**



PROJECT NUMBER

SHEET TITLE **SITE PLAN**





EXISTING LEGEND:

	00		LIST OF
O-PIPELINE VENT	-TELE. PED.	-TRAFFIC CONTROL BOX	ABBREVIATIONS U/G — UNDERGROUND
→ GAS METER □ -	-ELEC. PEDESTAL	□ -ROAD SIGN □-ELECTRIC MANHOLE	HC - HANDICAPPED CONC CONCRETE
7SZ → SIGNAL LIGHT ⊕ -	-WATER VALVE	GROUND LIGHT	RET. — RETAINING APPROX. — APPROXIMATE
PP → PIPELINE MRKR Ø →	-POWER POLE	- UΠLITY POLE	SAN. – SANITARY ASPH. – ASPHALT TYP. – TYPICAL
-MAIL BOX	-PULL BOX	© −GAS VALVE	BLDG. — BUILDING PED. — PEDESTAL PLTR. — PLANTER
—BUSH F.H.	FIRE HYDRANT	O-TEL. U.G. MRKR. T-TELE. MANHOLE	G/R — GAS REGULATOR G/L — GROUND LIGHT
T - CURB INLET W/ M.H. COVER	-TREE	E-ELEC. MANHOLE	TRANS — TRANSFORMER F.F. — FINISHED FLOOR
S -SAN. SEW. M.H.	-STM. SEW. M.H.	-STOCKADE FCE	C — CENTER LINE R.O.W — RIGHT—OF—WAY
€ –GUY WIRE	-GUARD POST	-BARB WIRE FCE	FCE. — FENCE BIA. — DIAMETER
O -CLEAN OUT	– TV PED – LIGHT POLE	-CHAIN LINK FCE	BLVD. — BOULEVARD B/L — BUILDING SETBACK LINE
● – FLAG POLE	MW MONITOR WELL	SO— WATER METER ☐C	ESMT. – EASEMENT A/S – AUTO-SPRINKLER
ET - ELEC TRANS ST	-STS ORM SEWER	— TRASH CAN	DIST. — DISTANCE BRNG. — BEARING
	T ——— DERGROUND MMUNICATION	SANITARY SEWER WATER LINE	W/UGS — WITH UNDERGROUND SERVICE ACCUMENTATION
UTA	NK ACCESS	-HANDICAP	MW — MONITOR WELL STAT. — STATUTORY M — MEASURED
-CONCRETE W.	-WATER HYDRANT	—IRON GRATE GRATE	DIMENSION P — PLAT DIMENSION IG — IRON GRATE
-TRAFFIC DIRECTI	ION F		R - RECORD DIMENSION RD - ROOF DRAIN
TR — TOP OF RIM FL — FLOW LINE	S/A	AUTO SPRINKLER	P.O.M. — POINT OF MEASUREMENT

DEMOLITION KEY NOTES

- DEPARTMENT FOR REMOVAL AND/OR POINT OF CONNECTION
- DEPARTMENT FOR REMOVAL AND/OR POINT OF CONNECTION

GreenbergFarrow

5500 Democracy Dr. Suite 125 Plano, TX 75024 t: 972 514 7641

PROJECT TEAM

This drawing is the property of the above referenced Professional and is not to be used for any purpose other than the specific project and site named herein, and cannot be reproduced in any manner without the

ISSUE/REVISION RECORD

DESCRIPTION 08-07-14 DEVELOPMENT PLAN

PROFESSIONAL IN CHARGE FARMAN SHIR, PE PROFESSIONAL ENGINEER LICENSE NO. 21307

PROJECT MANAGER MARLEY PHILLIPS **QUALITY CONTROL** KIEW KAM, PE

NICOLE NOVACK **PROJECT NAME**

FLORA VISTA

DRAWN BY

CIRCLE K

SAN JUAN COUNTY NEW MEXICO 819 NM 516



PROJECT NUMBER

SHEET TITLE

DEMOLITION PLAN


SHEET NUMBER


D1 EXISTING TO BE REMOVED

D2 EXISTING TO REMAIN

D5 LIMITS OF SAWCUT AND FULL DEPTH PAVEMENT REMOVAL D8 CONTRACTOR TO COORDINATE WITH LOCAL WATER SEWER

D9 CONTRACTOR TO COORDINATE WITH NEW MEXICO ENVIRONMENT





PROPOSED LEGEND:

PROPERTY LINE PROPOSED CURB & GUTTER PROPOSED DRAINAGE STRUCTURES (SEE GRADING/DRAINAGE PLANS) EXPANSION JOINT CONSTRUCTION JOINT CONTROL JOINT PROPOSED REGULAR DUTY CONCRETE

PAVEMENT. SEE SHEET C-7.0 PROPOSED HEAVY DUTY CONCRETE PAVING. SEE SHEET C-7.0



PROPOSED CONCRETE SIDEWALK

GENERAL PAVING NOTES:

1. CONTRACTOR MUST SECURE ALL NECESSARY PERMITS PRIOR TO STARTING WORK.

- 2. IF THE CONTRACTOR, IN THE COURSE OF THE WORK, FINDS ANY DISCREPANCIES BETWEEN THE PLANS AND THE PHYSICAL CONDITIONS OF THE LOCALITY, OR ANY ERRORS OR OMISSIONS IN THE PLANS OR IN THE LAYOUT AS GIVEN BY THE ENGINEER, IT SHALL BE HIS DUTY TO IMMEDIATELY INFORM THE ENGINEER, IN WRITING, AND THE ENGINEER WILL PROMPTLY VERIFY THE SAME. ANY WORK DONE AFTER SUCH A DISCOVERY, UNTIL AUTHORIZED, WILL BE AT THE CONTRACTOR'S RISK.
- 3. CONTRACTOR SHALL BE RESPONSIBLE FOR VERIFICATION OF ALL SETBACKS, EASEMENTS, AND DIMENSIONS SHOWN HEREON BEFORE BEGINNING CONSTRUCTION.
- 4. ALL CONSTRUCTION MATERIALS AND WORKMANSHIP SHALL BE IN ACCORDANCE TO THE STATE AND LOCAL GOVERNMENT AGENCY LATEST CONSTRUCTION SPECIFICATIONS AND DETAILS.
- 5. ALL HANDICAP SITE FEATURES SHALL BE CONSTRUCTED TO MEET ALL FEDERAL, STATE AND LOCAL CODE.
- 6. NOTIFY THE COUNTY INSPECTOR TWENTY-FOUR (24) HOURS BEFORE BEGINNING EACH PHASE OF CONSTRUCTION.
- 7. THE CONTRACTOR SHALL CAREFULLY PRESERVE BENCHMARKS, REFERENCE POINTS, AND STAKES.
- 8. ARCHITECTURAL PLANS ARE TO BE USED FOR BUILDING STAKE 9. ALL DIMENSIONS ARE FROM FACE OF BUILDING, CURB, AND WALL
- UNLESS OTHERWISE SPECIFIED ON PLANS. 10. CONTRACTOR SHALL MAINTAIN THE SITE IN A MANNER SO THAT WORKMEN AND PUBLIC SHALL BE PROTECTED FROM INJURY, AND
- ADJOINING PROPERTY PROTECTED FROM DAMAGE. 11. CONTRACTOR IS RESPONSIBLE FOR DAMAGE TO ANY EXISTING ITEM AND/OR MATERIAL INSIDE OR OUTSIDE CONTRACT LIMITS DUE
- TO CONSTRUCTION OPERATION. 12. ALL STREET SURFACES, DRIVEWAYS, CULVERTS, CURB AND GUTTERS, ROADSIDE DRAINAGE DITCHES AND OTHER STRUCTURES THAT ARE DISTURBED OR DAMAGED IN ANY MANNER AS A RESULT OF CONSTRUCTION SHALL BE REPLACED OR REPAIRED IN
- 13. ALL ROAD WORK SHALL BE PERFORMED IN ACCORDANCE WITH THE STATE AND LOCAL GOVERNMENT AGENCY SPECIFICATIONS.

PAVING KEY NOTES

- P1 MATCH EXISTING PAVEMENT ELEVATION
- P2 EXISTING PAVEMENT TO REMAIN
- P3 CONCRETE SIDEWALK
- P4 MATCH EXISTING SIDEWALK ELEVATIONS.
- P12 THICKENED EDGE OF PAVING

ACCORDANCE WITH THE SPECIFICATIONS.

GreenbergFarrow

5500 Democracy Dr. Suite 125 Plano, TX 75024 t: 972 514 7641

PROJECT TEAM

This drawing is the property of the above referenced Professional and is not to be used for any purpose other than the specific project and site named herein, and cannot be reproduced in any manner without the express written permission from the Professional

ISSUE/REVISION RECORD

DATE DESCRIPTION

08-07-14	DEVELOPMENT PLAN

PROFESSIONAL IN CHARGE FARMAN SHIR, PE PROFESSIONAL ENGINEER

LICENSE NO. 21307 **PROJECT MANAGER** MARLEY PHILLIPS **QUALITY CONTROL** KIEW KAM, PE **DRAWN BY**

PROJECT NAME

NICOLE NOVACK

CIRCLE K

SAN JUAN COUNTY NEW MEXICO


819 NM 516 **FLORA VISTA**



PROJECT NUMBER

SHEET TITLE

PAVING PLAN





CONSTRUCTION.

GRAPHIC SCALE

(IN FEET)

1 inch = 30 ft.

-TRAFFIC

CONTROL BOX

-ROAD SIGN

)-TELE. MANHOLE

SANITARY SEWER

WATER LINE

-HANDICAP

-TELE. PED.

-WATER VALVE

-PULL BOX

— T —— UNDERGROUND

COMMUNICATION

PROPERTY LINE

PROPOSED CONTOUR

SIDEWALK ELEVATION

CANOPY CLEARANCE

TOP OF CURB

GUTTER

EXISTING SPOT ELEVATION

NOTE: ALL PROPOSED SPOT

ELEVATIONS HAVE A BASE ELEVATION OF 5500 FEET

PROPOSED CURB & GUTTER

DRAINAGE SLOPE AND DIRECTION

PROPOSED 6" HDPE STORM SEWER PIPE

PROPOSED 12" OR LARGER STORM SEWER PIPE

LIST OF

APPROX. - APPROXIMATE

ABBREVIATIONS
U/G - UNDERGROUND

HC - HANDICAPPED

RET. – RETAINING

SAN. - SANITARY

ASPH. – ASPHALT

BLDG. — BUILDING PED. - PEDESTAL

PLTR. – PLANTER

G/R - GAS REGULATOR

TRANS - TRANSFORMER

R.O.W - RIGHT-OF-WAY

A/S - AUTO-SPRINKLER

UNDERGROUND

FCE. - FENCE ÐIA. — DIAMETER

METER ESMT. - EASEMENT

-IRON GRATE P - PLAT DIMENSION
GRATE IC - IRON CRATE

-AUTO SPRINKLER P.O.M. - POINT OF MEASUREMENT

BLVD. — BOULEVARD B/L - BUILDING SETBACK

DIST. - DISTANCE

BRNG. – BEARING

MW - MONITOR WELL

STAT. - STATUTORY

IG — IRON GRATE

RD — ROOF DRAIN

R - RECORD DIMENSION

G/L — GROUND LIGHT

TYP. - TYPICAL

-ELECTRIC MANHOLE CONC. - CONCRETE

ELEC. MANHOLE F.F. - FINISHED FLOOR

-STOCKADE FCE C - CENTER LINE

- 1. ALL GRADING AND SITE PREPARATION SHALL CONFORM WITH SPECIFICATIONS CONTAINED IN THE GEOTECHNICAL REPORT.
- 2. ALL CONSTRUCTION MATERIALS AND WORKMANSHIP SHALL BE IN ACCORDANCE TO THE COUNTY LATEST CONSTRUCTION SPECIFICATIONS AND DETAILS.
- 3. PRIOR TO ANY EXCAVATION OF THE PROJECT SITE, THE CONTRACTOR SHALL NOTIFY THE COUNTY 48 HOURS PRIOR TO THE START OF
- 4. THE CONTRACTOR SHALL CAREFULLY PRESERVE BENCHMARKS, REFERENCE POINTS AND STAKES.
- 5. ALL INDICATED ELEVATIONS ARE FINISHED ELEVATIONS.
- 6. FIELD VERIFY LOCATIONS, SIZES AND IF APPLICABLE INVERTS OF EXISTING UTILITIES FOR PROPOSED CONNECTIONS PRIOR TO CONSTRUCTION.
- LOCATE AND PROTECT ALL UTILITIES ASSOCIATED WITH THE PROJECT PRIOR TO CONSTRUCTION.
- 8. INSTALL SILT CONTROL MEASURES BEFORE BEGINNING SITE WORK. THESE MEASURES SHALL BE MAINTAINED THROUGHOUT CONSTRUCTION.
- 9. MAINTAIN PROPER SITE DRAINAGE AT ALL TIMES DURING CONSTRUCTION. PREVENT STORM WATER FROM RUNNING INTO OR STANDING IN EXCAVATED AREAS.
- 10. INSTALL ALL APPROPRIATE TREE PROTECTION MEASURES PRIOR TO GRADING.
- 11. CUT AND FILL SLOPES SHALL HAVE A MAXIMUM SLOPE OF 2:1.
- 12. ALL EXCAVATION SHALL INCLUDE CLEARING, STRIPPING AND STOCKPILING TOPSOIL, REMOVING UNSUITABLE MATERIALS. THE CONSTRUCTION OF EMBANKMENTS, CONSTRUCTION FILLS, AND THE FINAL SHAPING AND TRIMMING TO THE THE LINES AND GRADES SHOWN ON THE PLANS.
- 13. ALL TREES, BRUSH, AND ORGANIC TOPSOIL AND OTHER OBJECTIONABLE MATERIAL SHALL BE REMOVED, UNLESS OTHERWISE SPECIFIED, AND DISPOSED OF AT AN OFF-SITE LOCATION, WITH THE EXCEPTION THAT ENOUGH TOPSOIL SHALL BE RETAINED FOR RESPREAD AND GENERAL LANDSCAPING. AREAS WHICH ARE TO BE FILLED SHALL BE COMPACTED TO A MAXIMUM DENSITY OF 95% AS DETERMINED BY THE MODIFIED AASHTO COMPACTION TEST IN THE PAVED AREAS AND 85% IN THE OTHER AREAS.
- 14. STRIP AND STOCKPILE TOPSOIL. SPREAD FOUR (4) INCHES MINIMUM OF TOPSOIL ON LANDSCAPE AREAS AND REMOVE EXCESS TOPSOIL FROM SITE. PREPARE SUB-GRADE FOR PAVEMENT AND CURBS AND BACKFILL CURBS AFTER CURB CONSTRUCTION.
- 15. PROVIDE SUPPLY OF TOPSOIL FOR LANDSCAPE CONTRACTOR FOR INSTALLATION IN ALL LANDSCAPE ISLANDS.
- 16. PROVIDE AND INSTALL TOPSOIL IN DISTURBED AREAS TO BE GRASSED, TO INCLUDE PAVEMENT SHOULDERS AND DETENTION AREAS.
- 17. ALL EARTHWORK AND BASE COURSE FOR THE PARKING AREA SHALL BE COMPACTED TO A MINIMUM OF 95% MODIFIED LABORATORY DENSITY. CERTIFICATION SAID COMPACTION SHALL BE SUBMITTED BY THE CONTRACTOR TO THE ENGINEER, OR HIS/HER REPRESENTATIVE, PRIOR TO THE PLACEMENT OF THE BASE COURSE MATERIAL. BOTH PROOF ROLLING AND COMPACTION TESTING MUST BE APPROVED AND WITNESSED BY THE ENGINEER OR OWNER REPRESENTATIVE.
- 18. THE PAVEMENT SUBGRADE AND BASE COURSE MATERIAL SHALL BE INSPECTED AND APPROVED BY THE ENGINEER OR OWNER REPRESENTATIVE PRIOR TO CONSTRUCTING THE BASE AND SURFACE COURSES THEREON.
- 19. CONTRACTOR SHALL PROVIDE POSITIVE DRAINAGE TO ALL INLETS AND CATCH BASINS. AREAS OF SURFACE PONDING SHALL BE CORRECTED BY CONTRACTOR AT NO ADDITIONAL EXPENSE TO THE OWNER.
- 20. IF AREAS ARE DISTURBED BEYOND PROPOSED GRADES BY NEGLIGENCE OF THE CONTRACTOR, THE CONTRACTOR SHALL BE HELD RESPONSIBLE FOR ANY REGRADING OR REPAIR TO MATCH ORIGINAL EXISTING CONDITIONS.
- 21. SHORING SHALL BE DONE AS NECESSARY FOR THE PROTECTION OF THE WORK AND FOR THE SAFETY OF PERSONNEL. SHORING SHALL BE IN ACCORDANCE WITH ALL O.S.H.A AND LOCAL REGULATIONS.
- 22. STRUCTURES FOR STORM SEWERS SHALL BE IN ACCORDANCE WITH THESE IMPROVEMENT PLANS AND THE APPLICABLE STANDARD SPECIFICATIONS. WHERE GRANULAR TRENCH BACKFILL IS REQUIRED AROUND THESE STRUCTURES, THE COST SHALL BE CONSIDERED AS INCIDENTAL AND SHALL BE INCLUDED IN THE CONTRACT UNIT PRICE FOR THE STRUCTURE.
- 23. CONFIRM INVERTS OF ALL EXISTING STORM INLETS AND SANITARY SEWER MANHOLES BEFORE COMMENCING CONSTRUCTION.
- 24. ALL STORM SEWER LINES 18"-54" DIAMETER ARE TO BE REINFORCED CONCRETE PIPE ACCORDING TO ASTM C-76 TYPE III, UNLESS OTHERWISE SPECIFIED ON PLANS.
- 25. A GEOTEXTILE MATTING (LANDLOCK TRM 450 OR EQUIVALENT) SHALL BE USED FOR EROSION CONTROL AN ALL SLOPES GREATER THAN 3H:1V.
- 26. DRAINAGE STRUCTURES SHALL BE MAINTAINED BY PROPERTY OWNERS.
- 27. CONTRACTOR SHALL ADHERE TO PROPOSED GRADES ALONG CREEKS, ESPECIALLY IN THE AREA OF THE PROPOSED DETENTION POND. IF AREAS ARE DISTURBED BEYOND PROPOSED GRADES BY NEGLIGENCE OF THE CONTRACTOR, THE CONTRACTOR SHALL BE HELD RESPONSIBLE FOR ANY PENALTIES INCURRED.
- 28. ALL PROPOSED SPOT ELEVATIONS SHOWN INDICATE FINISHED GRADED ELEVATIONS AT EDGE OF PAVEMENT AND/OR GRADE BREAKS, UNLESS OTHERWISE NOTED.

5500 Democracy Dr. Suite 125 Plano, TX 75024 t: 972 514 7641

PROJECT TEAM

This drawing is the property of the above referenced Professional and is not to be used for any purpose other than the specific project and site named herein, and cannot be reproduced in any manner without the

ISSUE/REVISION RECORD

DESCRIPTION 08-07-14 DEVELOPMENT PLAN

PROFESSIONAL IN CHARGE FARMAN SHIR, PE PROFESSIONAL ENGINEER LICENSE NO. 21307

PROJECT MANAGER MARLEY PHILLIPS **QUALITY CONTROL** KIEW KAM, PE **DRAWN BY**

NICOLE NOVACK

PROJECT NAME

CIRCLE K

SAN JUAN COUNTY NEW MEXICO 819 NM 516







PROJECT NUMBER

SHEET TITLE

GRADING PLAN





(IN FEET)
1 inch = 30 ft.

EXISTING LEGEND:

i.			
O-PIPELINE VENT	□ -TELE. PED.	TRAFFIC CONTROL BOX ROAD SIGN	LIST OF ABBREVIATIONS U/G - UNDERGROUND
G -GAS METER	□ −ELEC. PEDESTAL		HC — HANDICAPPED CONC. — CONCRETE
Z ☐ -SIGNAL LIGHT	⊕ -WATER VALVE	GROUND LIGHT	RET. — RETAINING APPROX. — APPROXIMATE SAN. — SANITARY
▲ -PIPELINE MRKR		- UTILITY POLE	ASPH. – ASPHALT TYP. – TYPICAL
-MAIL BOX	☐ —PULL BOX	G -GAS VALVE	BLDG. — BUILDING PED. — PEDESTAL PLTR. — PLANTER
⊕ –BUSH	-FIRE HYDRANT F.H.	O-TEL. U.G. MRKR.	G/R — GAS REGULATOR G/L — GROUND LIGHT
U - CURB INLET W/ M.H. COVER	-TREE	E-ELEC. MANHOLE	TRANS — TRANSFORMER F.F. — FINISHED FLOOR
SS -SAN. SEW. M.H.	S -STM. SEW. M.H.	-STOCKADE FCE	C — CENTER LINE R.O.W — RIGHT—OF—WAY
€ -GUY WIRE	G-GUARD POST	-BARB WIRE FCE	FCE. — FENCE BIA. — DIAMETER
C -CLEAN OUT		-CHAIN LINK FCE	BLVD. — BOULEVARD B/L — BUILDING SETBACK LINE
O - FLAG POLE	MW MONITOR WEL	L TC WATER METER	ESMT. – EASEMENT A/S – AUTO-SPRINKLER
ET - ELEC TRANS	STS STORM SEWER	□ − TRASH CAN ——— SS———	DIST. — DISTANCE BRNG. — BEARING
—F/O—— FIBER OPTIC	T UNDERGROUND COMMUNICATION	SANITARY SEWER WATER LINE	W/UGS — WITH UNDERGROUND SERVICE
UTA → UNDERGROUN	D TANK ACCESS	WATER LINE -HANDICAP	MW — MONITOR WELL STAT. — STATUTORY M — MEASURED
-CONCRETE	W.H.	-IRON GRATE GRATE	DIMENSION P — PLAT DIMENSION IG — IRON GRATE
-TRAFFIC DI	RECTION	FR −FIRE RISER	R - RECORD DIMENSION RD - ROOF DRAIN
TR — TOP OF RII FL — FLOW LINE	M	-AUTO SPRINKLER	P.O.M. — POINT OF MEASUREMENT

PROPOSED LEGEND:

PROPOSED L	LEGEND:
	PROPERTY LINE
	PROPOSED CURB & GUTTER
XXXX	PROPOSED CONTOUR
STM->	PROPOSED 6" HDPE STORM SEWER PIPE
── STM-> ─	PROPOSED 12" OR LARGER STORM SEWER PIPE
୍ୟ ପ୍ର	

DRAINAGE SLOPE AND DIRECTION

GRADING KEY NOTES

- G2 STORM SEWER (SEE NOTE FOR TYPE, SIZE AND SLOPE)
- G5 STORM SEWER CLEAN-OUT
- G6 CURB INLET
- G9 GRATE INLET.
- G13 JUNCTION BOX
- G24 CONNECT DOWN SPOUTS UNDERGROUND TO STORM PIPE (SEE NOTE FOR NUMBER AND SIZE)
- G25 CONNECT TO EXISTING STORM INLET. (CONTRACTOR TO FIELD VERIFY LOCATION AND ELEVATION)
- G26A RIP RAP PAD
- G50 WYE CONNECTION (SEE NOTE FOR TYPE AND SIZE)
- G51 45° BEND (SEE NOTE FOR SIZE)

GreenbergFarrow

5500 Democracy Dr. Suite 125 Plano, TX 75024 t: 972 514 7641

PROJECT TEAM

COPYRIGHT NOTICE
This drawing is the property of the above referenced Professional and is not to be used for any purpose other than the specific project and site named herein, and cannot be reproduced in any manner without the express written permission from the Professional

ISSUE/REVISION RECORD

DATE DESCRIPTION

08-07-14 DEVELOPMENT PLAN

PROFESSIONAL IN CHARGE FARMAN SHIR, PE PROFESSIONAL ENGINEER LICENSE NO. 21307

PROJECT MANAGER
MARLEY PHILLIPS

QUALITY CONTROL
KIEW KAM, PE

DRAWN BY

NICOLE NOVACK
PROJECT NAME

FLORA VISTA

CIRCLE K

SAN JUAN COUNTY NEW MEXICO 819 NM 516




PROJECT NUMBER

SHEET TITLE

DRAINAGE PLAN

SHEET NUMBER

C-4.0




- B. THE TEMPORARY PARKING AND STORAGE AREA SHALL ALSO BE USED AS THE EQUIPMENT MAINTENANCE AREA, EQUIPMENT CLEANING AREA, EMPLOYEE COORDINATED WITH THE OWNERS CONSTRUCTION MANAGER.
- C. ALL WASH WATER (CONCRETE TRUCKS, VEHICLE CLEANING, EQUIPMENT CLEANING, ETC.) SHALL BE DISPOSED OF IN A MANNER THAT PREVENTS
- MAINTAIN ON THE SITE OR HAVE READILY AVAILABLE SUFFICIENT OIL AND GREASE ABSORBING MATERIALS AND FLOTATION BOOMS TO CONTAIN AND
- E. DUST ON THE SITE SHALL BE CONTROLLED BY SPRAYING WATER ON DRY AREAS OF THE SITE. THE USE OF MOTOR OILS AND OTHER PETROLEUM BASED
- NO RUBBISH, TRASH, GARBAGE, OR OTHER SUCH MATERIALS SHALL BE
- PLAN. AND IN THE STORM WATER POLLUTION PREVENTION PLAN, SHALL BE INITIATED AS SOON AS PRACTICABLE.
- BE RETAINED BY VEGETATIVE COVER, AND MUST BE PROVIDED WITH A GROUND
- A PERMANENT GROUND COVER, SUFFICIENT RESTRAIN EROSION, MUST BE PROVIDED WITHIN THE SHORTER OF 15 WORKING OR 90 CALENDAR DAYS (IF IN A HIGH QUALITY ZONE, THE SHORTER OF 15 WORKING OR 60 CALENDAR DAYS) AFTER COMPLETION OF CONSTRUCTION OR DEVELOPMENT ON ANY PORTION OF THE TRACT.
- J. IF THE ACTION OF VEHICLES TRAVELING OVER THE GRAVEL CONSTRUCTION ENTRANCES IS NOT SUFFICIENT TO REMOVE THE MAJORITY OF DIRT OR MUD, THEN THE TIRES MUST BE WASHED BEFORE THE VEHICLES ENTER A PUBLIC ROAD. IF WASHING IS USED, PROVISIONS MUST BE MADE TO INTERCEPT THE WASH WATER AND TRAP THE SEDIMENT BEFORE IT IS CARRIED OFF THE SITE. THE EXACT LOCATIONS SHALL BE COORDINATED WITH THE OWNERS CONSTRUCTION MANAGER.
- ONTO ROADWAYS OR INTO STORM DRAINS MUST BE REMOVED IMMEDIATELY.
- L. CONTRACTORS OR SUBCONTRACTORS WILL BE RESPONSIBLE FOR REMOVING SEDIMENT IN THE DETENTION POND AFTER THE STABILIZATION OF THE SITE AND ANY SEDIMENT THAT MAY HAVE COLLECTED IN THE STORM SEWER DRAINAGE SYSTEMS. CONTRACTORS OR SUBCONTRACTORS WILL ALSO BE RESPONSIBLE TO CLEAN THE SWALE FROM ANY SEDIMENT IF NECESSARY.
- M. IF SOIL STOCKPILING IS EMPLOYED ON THE SITE, SILT FENCES SHALL BE USED TO HELP CONTAIN THE SEDIMENT.
- N. SLOPES SHALL BE LEFT IN A ROUGHENED CONDITION DURING THE GRADING PHASE TO REDUCE RUNOFF VELOCITIES AND EROSION.
- DANGEROUS. IN ALL CASES, LOCAL ORDINANCES AND REGULATIONS REGARDING HEALTH AND SAFETY MUST BE ADHERED TO.
- DISPOSED OF WITHIN 30 DAYS AFTER FINAL STABILIZATION. FINAL STABILIZATION HAS OCCURRED WHEN ALL SOIL DISTURBING ACTIVITIES ARE COMPLETED AND A UNIFORM PERENNIAL VEGETATIVE COVER WITH A DENSITY OF 70% OF THE COVER FOR UNPAVED AREAS AND AREAS NOT COVERED BY
- Q. DUE TO THE GRADE CHANGES DURING THE DEVELOPMENT OF THE PROJECT, THE CONTRACTOR SHALL BE RESPONSIBLE FOR ADJUSTING THE EROSION CONTROL MEASURES (SILT FENCES, SILT DIKES, ETC.) TO HELP PREVENT EROSION AND STORM WATER POLLUTION.
- R. ALL OFF-SITE CONSTRUCTION SHALL BE STABILIZED AT THE END OF EACH WORKING DAY, THIS INCLUDES BACKFILLING OF TRENCHES FOR STORM DRAINS & UTILITY CONSTRUCTION AND PLACEMENT OF GRAVEL OR BITUMINOUS PAVING FOR ROAD CONSTRUCTION.

GENERAL EROSION NOTES

- A. ALL CONTRACTORS AND SUBCONTRACTORS INVOLVED WITH STORM WATER POLLUTION PREVENTION SHALL OBTAIN A COPY OF THE STORM WATER POLLUTION PREVENTION PLAN AND THE STATE OF <u>NEW MEXICO</u> NPDES GENERAL PERMIT FOR STORM WATER DISCHARGES AND BECOME FAMILIAR WITH
- BREAK AREA, AND AREA FOR LOCATING PORTABLE FACILITIES, OFFICE TRAILERS, AND TOILET FACILITIES. THE EXACT LOCATIONS SHALL BE
- CONTACT BETWEEN THESE MATERIALS AND STORM WATER THAT IS DISCHARGED
- CLEAN-UP FUEL OR CHEMICAL SPILLS AND LEAKS.
- OR TOXIC LIQUIDS FOR DUST SUPPRESSION OPERATIONS IS PROHIBITED.
- DISCHARGED INTO DRAINAGE DITCHES OR WATERS OF THE STATE. G. ALL STORM WATER POLLUTION PREVENTION MEASURES PRESENTED ON THIS
- H. NEW OR AFFECTED CUT OR FILLED SLOPES MUST BE AT AN ANGLE THAT CAN
- COVER SUFFICIENT TO RETAIN EROSION WITHIN 21 CALENDAR DAYS OF COMPLETION OF ANY PHASE (ROUGH OR FINAL) OF GRADING.
- K. ALL MATERIALS SPILLED, DROPPED, WASHED, OR TRACKED FROM VEHICLES

- O. SEDIMENT BASINS ARE ATTRACTIVE TO CHILDREN AND CAN BE VERY
- P. ALL TEMPORARY EROSION AND SEDIMENT CONTROL MEASURES SHALL BE PERMANENT STRUCTURES HAS BEEN EMPLOYED.



GRAPHIC SCALE (IN FEET) 1 inch = 30 ft.

PROPOSED

BOUNDARY LINE —xx——— CONTOUR ELEVATIONS —SF——— SILT FENCE (SEE DETAIL SHEETS) LIMIT OF DISTURBED AREA

PROJECT INFORMATION

THE PROPOSED PROJECT IS CONSTRUCTING A GAS STATION CONSISTING OF A 4.480 S.F. CONVENIENT STORE, AN OVERHEAD CANOPY WITH <u>8</u> PUMPING ISLANDS AND ASSOCIATED PARKING AREA.

ACREAGE OF SITE IS 1.96 ACRES.

DISTURBED ACREAGE OF SITE (INCLUDING OFF-SITE WORK) IS 3.13 ACRES.

ANTICIPATED CONSTRUCTION START DATE IS JUNE 2014 AND COMPLETION DATE IS NOVEMBER 2014.

CIRCLE K CONTRACTOR TO TAKE APPROPRIATE MEASURES TO KEEP SEDIMENT FROM ESCAPING SITE AND ALL ACCUMULATED SEDIMENT SHALL BE CLEANED OUT AND REMOVED FROM SITE.

VTC VEHICLE TRACKING CONTROL

CFS COMPOST FILTER SOCK

CWA CONCRETE WASHOUT AREA TS TEMPORARY STORAGE AREA

SSA STABILIZED STAGING AREA

RR RIP RAP PAD

SEQUENCE OF CONSTRUCTION

- PHASE I

 1. INSTALL STABILIZED CONSTRUCTION ENTRANCES.

 2. PREPARE TEMPORARY PARKING AND STORAGE AREA. CONSTRUCT THE SILT FENCES ON THE SITE. INSTALL EROSION LOG AS INDICATED ON THE PLAN
- CLEAR AND GRUB THE SITE. 6. BEGIN GRADING THE SITE.

SITE IS STABILIZED).

- 7. START CONSTRUCTION OF BUILDING PAD AND STRUCTURES.
- 8. TEMPORARILY SEED DENUDED AREAS. INSTALL UTILITIES, UNDERDRAINS, STORM SEWERS, CURBS AND GUTTERS. 10. INSTALL EROSION LOG AS SHOWN ON THE PLANS.

15. REMOVE ALL TEMPORARY EROSION AND SEDIMENT CONTROL DEVICES (ONLY IF

11. INSTALL RIP RAP AROUND OUTLET STRUCTURES. 12. PREPARE SITE FOR PAVING. 13 PAVE SITE. 14. COMPLETE GRADING AND INSTALL PERMANENT SEEDING AND PLANTING.

SURFACE STABILIZATION MEASURES

	•		,
KEY	PRACTICE	DESCRIPTION	NOTES
M	DISTURBED AREA STABILIZATION(W/ MULCHING ONLY)	Temporary protection for disturbed areas; as an erosion retardant cover when temporary grassing is inapplicable.	Straw (1-2 tons/acre), Wood chips (5-6 tons/acre), Wood fiber (0.5-1 tons/acre), Bark (35 cy/acre), Corn stalks (4-6 tons / acre), or Nets/Mats/Chemical stabilizers applicable
TS	DISTURBED AREA STABILIZATION(W/ TEMP. SEEDING)	Planting rapid—growing annual grasses, small grains, or legumes to provide initial, temporary cover for erosion control on disturbed areas.	May—Aug.: German millet (40 lbs./ac), Aug.—Dec.: Rye grain (120 lbs./ac), Jan.—May: Mixture of Rye grain (120 lbs./ac) and Kobe lespedeza (50 lbs./ac) 750 (1000 lbs.—for Fall) lbs./ac of 10—10—10 fertilizer
PS	DISTURBED AREA STABILIZATION(W/ PERM. SEEDING)	Controlling runoff and preventing erosion by establishing a perennial vegetative cover with seed.	Mixture of Tall fescue (80 lbs./ac) and Kobe lespedeza (40 lbs./ac) with 1000 lbs./ac of 10-10-10 fertilizer and 4,000 lbs./ac of lime *May-Aug.: Add 10 lbs./ac German millet *OctFeb.: Add 40 lbs./ac Rye grain
SO	DISTURBED AREA STABILIZATION(W/ PERM. SODDING)	Transplanting vegetative sections of plant materials to promptly stabilize areas that are subject to erosion.	Warm Season: Hybrid Bermuda grass, Zaysiagrass, Centipede grass, or St Augustine grass Cool Season: Tall fescue/Kentucky bluegrass
DC	DUST CONTROL	Utilize dust control methods whenever there are offsite impacts, especially periods of drought until final stabilization is reached.	Phasing the project, vegetative cover, Mulch, sprinkling water, spray—on—adhesive, calcium chloride, barriers, etc.

SOIL EROSION/SEDIMENTATION	NC	CO	NTF	ROL	Ol	PER	RAT	ION	TI	ME	SC	ΉE	DUI	_E										
NOTE: GENERAL CONTRACTOR TO	CC	MPl	ETE	TA	BLE	E WI	TH	THE	IR :	SPE	CIFIC	C P	ROJ	ECT	SC	HED	ULE	-						
CONSTRUCTION SEQUENCE	JAN	FEB	MAR	APR	MAY	JUN	JUL	AUG	SEP	ОСТ	NOV	DEC	JAN	FEB	MAR	APR	MAY	JUN	JUL	AUG	SEP	ОСТ	NOV	DEC
TEMPORARY CONTROL MEASURES																								
STRIP & STOCKPILE TOPSOIL																								
STORM FACILITIES																								
TEMPORARY CONSTRUCTION ROADS																								
FOUNDATION / BUILDING CONSTRUCTION																								
SITE CONSTRUCTION																								
PERMANENT CONTROL STRUCTURES																								
FINISH GRADING																								
LANDSCAPING/SEED/FINAL STABILIZATION																								
	•	•	•	•	•			•	•									•				•		

24 HR EMERGENCY CONTACT:

MIKE RUIZ- 915.595.0853

5500 Democracy Dr. Suite 125 Plano, TX 75024 t: 972 514 7641

PROJECT TEAM

This drawing is the property of the above referenced Professional and is not to be used for any purpose other than the specific project and site named herein, and cannot be reproduced in any manner without the

ISSUE/REVISION RECORD DESCRIPTION

08-07-14 DEVELOPMENT PLAN

PROFESSIONAL IN CHARGE FARMAN SHIR, PE PROFESSIONAL ENGINEER

LICENSE NO. 21307 **PROJECT MANAGER** MARLEY PHILLIPS **QUALITY CONTROL** KIEW KAM, PE

NICOLE NOVACK

FLORA VISTA

DRAWN BY

PROJECT NAME CIRCLE K


SAN JUAN COUNTY NEW MEXICO 819 NM 516



PROJECT NUMBER

SHEET TITLE


EROSION CONTROL PLAN PHASE I



GENERAL EROSION NOTES

- A. ALL CONTRACTORS AND SUBCONTRACTORS INVOLVED WITH STORM WATER POLLUTION PREVENTION SHALL OBTAIN A COPY OF THE STORM WATER POLLUTION PREVENTION PLAN AND THE STATE OF <u>NEW MEXICO</u> NPDES GENERAL PERMIT FOR STORM WATER DISCHARGES AND BECOME FAMILIAR WITH
- B. THE TEMPORARY PARKING AND STORAGE AREA SHALL ALSO BE USED AS THE EQUIPMENT MAINTENANCE AREA, EQUIPMENT CLEANING AREA, EMPLOYEE BREAK AREA, AND AREA FOR LOCATING PORTABLE FACILITIES, OFFICE TRAILERS, AND TOILET FACILITIES. THE EXACT LOCATIONS SHALL BE COORDINATED WITH THE OWNERS CONSTRUCTION MANAGER.
- C. ALL WASH WATER (CONCRETE TRUCKS, VEHICLE CLEANING, EQUIPMENT CLEANING, ETC.) SHALL BE DISPOSED OF IN A MANNER THAT PREVENTS CONTACT BETWEEN THESE MATERIALS AND STORM WATER THAT IS DISCHARGED
- D. MAINTAIN ON THE SITE OR HAVE READILY AVAILABLE SUFFICIENT OIL AND GREASE ABSORBING MATERIALS AND FLOTATION BOOMS TO CONTAIN AND CLEAN-UP FUEL OR CHEMICAL SPILLS AND LEAKS.
- E. DUST ON THE SITE SHALL BE CONTROLLED BY SPRAYING WATER ON DRY AREAS OF THE SITE. THE USE OF MOTOR OILS AND OTHER PETROLEUM BASED OR TOXIC LIQUIDS FOR DUST SUPPRESSION OPERATIONS IS PROHIBITED.
- F. NO RUBBISH, TRASH, GARBAGE, OR OTHER SUCH MATERIALS SHALL BE DISCHARGED INTO DRAINAGE DITCHES OR WATERS OF THE STATE.
- G. ALL STORM WATER POLLUTION PREVENTION MEASURES PRESENTED ON THIS PLAN, AND IN THE STORM WATER POLLUTION PREVENTION PLAN, SHALL BE INITIATED AS SOON AS PRACTICABLE.
- H. NEW OR AFFECTED CUT OR FILLED SLOPES MUST BE AT AN ANGLE THAT CAN BE RETAINED BY VEGETATIVE COVER, AND MUST BE PROVIDED WITH A GROUND COVER SUFFICIENT TO RETAIN EROSION WITHIN 21 CALENDAR DAYS OF COMPLETION OF ANY PHASE (ROUGH OR FINAL) OF GRADING.
- A PERMANENT GROUND COVER, SUFFICIENT RESTRAIN EROSION, MUST BE PROVIDED WITHIN THE SHORTER OF 15 WORKING OR 90 CALENDAR DAYS (IF IN A HIGH QUALITY ZONE, THE SHORTER OF 15 WORKING OR 60 CALENDAR DAYS) AFTER COMPLETION OF CONSTRUCTION OR DEVELOPMENT ON ANY PORTION OF THE TRACT.
- IF THE ACTION OF VEHICLES TRAVELING OVER THE GRAVEL CONSTRUCTION ENTRANCES IS NOT SUFFICIENT TO REMOVE THE MAJORITY OF DIRT OR MUD, THEN THE TIRES MUST BE WASHED BEFORE THE VEHICLES ENTER A PUBLIC ROAD. IF WASHING IS USED, PROVISIONS MUST BE MADE TO INTERCEPT THE WASH WATER AND TRAP THE SEDIMENT BEFORE IT IS CARRIED OFF THE SITE. THE EXACT LOCATIONS SHALL BE COORDINATED WITH THE OWNERS CONSTRUCTION MANAGER.
- K. ALL MATERIALS SPILLED, DROPPED, WASHED, OR TRACKED FROM VEHICLES ONTO ROADWAYS OR INTO STORM DRAINS MUST BE REMOVED IMMEDIATELY.
- L. CONTRACTORS OR SUBCONTRACTORS WILL BE RESPONSIBLE FOR REMOVING SEDIMENT IN THE DETENTION POND AFTER THE STABILIZATION OF THE SITE AND ANY SEDIMENT THAT MAY HAVE COLLECTED IN THE STORM SEWER DRAINAGE SYSTEMS. CONTRACTORS OR SUBCONTRACTORS WILL ALSO BE RESPONSIBLE TO CLEAN THE SWALE FROM ANY SEDIMENT IF NECESSARY.
- M. IF SOIL STOCKPILING IS EMPLOYED ON THE SITE, SILT FENCES SHALL BE USED TO HELP CONTAIN THE SEDIMENT.
- N. SLOPES SHALL BE LEFT IN A ROUGHENED CONDITION DURING THE GRADING PHASE TO REDUCE RUNOFF VELOCITIES AND EROSION.
- O. SEDIMENT BASINS ARE ATTRACTIVE TO CHILDREN AND CAN BE VERY DANGEROUS. IN ALL CASES, LOCAL ORDINANCES AND REGULATIONS REGARDING HEALTH AND SAFETY MUST BE ADHERED TO.
- P. ALL TEMPORARY EROSION AND SEDIMENT CONTROL MEASURES SHALL BE DISPOSED OF WITHIN 30 DAYS AFTER FINAL STABILIZATION. FINAL STABILIZATION HAS OCCURRED WHEN ALL SOIL DISTURBING ACTIVITIES ARE COMPLETED AND A UNIFORM PERENNIAL VEGETATIVE COVER WITH A DENSITY OF 70% OF THE COVER FOR UNPAVED AREAS AND AREAS NOT COVERED BY PERMANENT STRUCTURES HAS BEEN EMPLOYED.
- Q. DUE TO THE GRADE CHANGES DURING THE DEVELOPMENT OF THE PROJECT, THE CONTRACTOR SHALL BE RESPONSIBLE FOR ADJUSTING THE EROSION CONTROL MEASURES (SILT FENCES, SILT DIKES, ETC.) TO HELP PREVENT EROSION AND STORM WATER POLLUTION.
- R. ALL OFF-SITE CONSTRUCTION SHALL BE STABILIZED AT THE END OF EACH WORKING DAY, THIS INCLUDES BACKFILLING OF TRENCHES FOR STORM DRAINS & UTILITY CONSTRUCTION AND PLACEMENT OF GRAVEL OR BITUMINOUS PAVING FOR ROAD CONSTRUCTION.

GRAPHIC SCALE



PROPOSED

BOUNDARY LINE -xx---- CONTOUR ELEVATIONS —SF——— SILT FENCE (SEE DETAIL SHEETS) LIMIT OF DISTURBED AREA

PROJECT INFORMATION

THE PROPOSED PROJECT IS CONSTRUCTING A GAS STATION CONSISTING OF A 4.480 S.F. CONVENIENT STORE, AN OVERHEAD CANOPY WITH <u>8</u> PUMPING ISLANDS AND ASSOCIATED PARKING AREA.

ACREAGE OF SITE IS 1.96 ACRES.

DISTURBED ACREAGE OF SITE (INCLUDING OFF-SITE WORK) IS 3.13 ACRES.

ANTICIPATED CONSTRUCTION START DATE IS JUNE 2014 AND COMPLETION DATE IS NOVEMBER 2014.

CIRCLE K CONTRACTOR TO TAKE APPROPRIATE MEASURES TO KEEP SEDIMENT FROM ESCAPING SITE AND ALL ACCUMULATED SEDIMENT SHALL BE CLEANED OUT AND REMOVED FROM SITE.

VTC VEHICLE TRACKING CONTROL

CFS COMPOST FILTER SOCK

CWA CONCRETE WASHOUT AREA TS TEMPORARY STORAGE AREA

SSA STABILIZED STAGING AREA RR RIP RAP PAD

SEQUENCE OF CONSTRUCTION

- PHASE I

 1. INSTALL STABILIZED CONSTRUCTION ENTRANCES.

 2. PREPARE TEMPORARY PARKING AND STORAGE AREA.
- CONSTRUCT THE SILT FENCES ON THE SITE. INSTALL EROSION LOG AS INDICATED ON THE PLAN
- . CLEAR AND GRUB THE SITE. 6. BEGIN GRADING THE SITE.

- 7. START CONSTRUCTION OF BUILDING PAD AND STRUCTURES. 8. TEMPORARILY SEED DENUDED AREAS.
- INSTALL UTILITIES, UNDERDRAINS, STORM SEWERS, CURBS AND GUTTERS. 10. INSTALL EROSION LOG AS SHOWN ON THE PLANS.
- 11. INSTALL RIP RAP AROUND OUTLET STRUCTURES. 12. PREPARE SITE FOR PAVING.
- 13 PAVE SITE 14. COMPLETE GRADING AND INSTALL PERMANENT SEEDING AND PLANTING.
- 15. REMOVE ALL TEMPORARY EROSION AND SEDIMENT CONTROL DEVICES (ONLY IF SITE IS STABILIZED).

SURFACE STABILIZATION MEASURES

CLEANED IMMEDIATELY BY A METHOD OTHER THAN FLUSHING.

KEY	PRACTICE	DESCRIPTION	NOTES
M	DISTURBED AREA STABILIZATION(W/ MULCHING ONLY)	Temporary protection for disturbed areas; as an erosion retardant cover when temporary grassing is inapplicable.	Straw (1-2 tons/acre), Wood chips (5-6 tons/acre), Wood fiber (0.5-1 tons/acre), Bark (35 cy/acre), Corn stalks (4-6 tons / acre), or Nets/Mats/Chemical stabilizers applicable
TS	DISTURBED AREA STABILIZATION(W/ TEMP. SEEDING)	Planting rapid—growing annual grasses, small grains, or legumes to provide initial, temporary cover for erosion control on disturbed areas.	May-Aug.: German millet (40 lbs./ac), AugDec.: Rye grain (120 lbs./ac), JanMay: Mixture of Rye grain (120 lbs./ac) and Kobe lespedeza (50 lbs./ac) 750 (1000 lbsfor Fall) lbs./ac of 10-10-10 fertilizer
PS	DISTURBED AREA STABILIZATION(W/ PERM. SEEDING)	Controlling runoff and preventing erosion by establishing a perennial vegetative cover with seed.	Mixture of Tall fescue (80 lbs./ac) and Kobe lespedeza (40 lbs./ac) with 1000 lbs./ac of 10-10-10 fertilizer and 4,000 lbs./ac of lime *May-Aug.: Add 10 lbs./ac German millet *OctFeb.: Add 40 lbs./ac Rye grain
SO	DISTURBED AREA STABILIZATION(W/ PERM. SODDING)	Transplanting vegetative sections of plant materials to promptly stabilize areas that are subject to erosion.	Warm Season: Hybrid Bermuda grass, Zaysiagrass, Centipede grass, or St Augustine grass Cool Season: Tall fescue/Kentucky bluegrass
(DC)	DUST CONTROL	Utilize dust control methods whenever there are offsite impacts, especially periods of drought until final stabilization is reached.	Phasing the project, vegetative cover, Mulch, sprinkling water, spray—on—adhesive, calcium chloride, barriers, etc.

SOIL EROSION/SEDIMENTATION	NC	СО	NTF	ROL	. 01	PER	RAT	ION	TI	ME	SC	HE	DUI	_E										
NOTE: GENERAL CONTRACTOR TO	CC	MPI	LETE	T/	ABLE	. WI	TH	THE	IR :	SPE	CIFIC	СР	ROJ	ECT	SC	HED	ULE	-						
CONSTRUCTION SEQUENCE	JAN	FEB	MAR	APR	MAY	JUN	JUL	AUG	SEP	ОСТ	NOV	DEC	JAN	FEB	MAR	APR	MAY	JUN	JUL	AUG	SEP	ОСТ	NOV	DEC
TEMPORARY CONTROL MEASURES																								
STRIP & STOCKPILE TOPSOIL																								
STORM FACILITIES																								
TEMPORARY CONSTRUCTION ROADS																								
FOUNDATION / BUILDING CONSTRUCTION																								
SITE CONSTRUCTION																								
PERMANENT CONTROL STRUCTURES																								
FINISH GRADING																								
LANDSCAPING/SEED/FINAL STABILIZATION																								

24 HR EMERGENCY CONTACT:

MIKE RUIZ- 915.595.0853

5500 Democracy Dr. Suite 125 Plano, TX 75024 t: 972 514 7641

PROJECT TEAM

COPYRIGHT NOTICE This drawing is the property of the above referenced Professional and is not to be used for any purpose other than the specific project and site named herein, and cannot be reproduced in any manner without the

ISSUE/REVISION RECORD

DESCRIPTION 08-07-14 DEVELOPMENT PLAN

PROFESSIONAL IN CHARGE FARMAN SHIR, PE PROFESSIONAL ENGINEER

LICENSE NO. 21307 **PROJECT MANAGER** MARLEY PHILLIPS **QUALITY CONTROL** KIEW KAM, PE

NICOLE NOVACK **PROJECT NAME**

DRAWN BY

CIRCLE K

SAN JUAN COUNTY NEW MEXICO 819 NM 516

FLORA VISTA




PROJECT NUMBER

SHEET TITLE **EROSION CONTROL**

SHEET NUMBER

PLAN PHASE II




VTC-1. AGGREGATE VEHICLE TRACKING CONTROL

Urban Drainage and Flood Control Distric

Urban Storm Drainage Criteria Manual Volume 3

VTC-3



MM-1

CWA

MM-1

CWA MAINTENANCE NOTES

Concrete Washout Area (CWA)

1. INSPECT BMPs EACH WORKDAY, AND MAINTAIN THEM IN EFFECTIVE OPERATING CONDITION. MAINTENANCE OF BMPs SHOULD BE PROACTIVE, NOT REACTIVE. INSPECT BMPs AS SOON AS POSSIBLE (AND ALWAYS WITHIN 24 HOURS) FOLLOWING A STORM THAT CAUSES SURFACE EROSION, AND PERFORM NECESSARY MAINTENANCE.

2. FREQUENT OBSERVATIONS AND MAINTENANCE ARE NECESSARY TO MAINTAIN BMPs IN EFFECTIVE OPERATING CONDITION. INSPECTIONS AND CORRECTIVE MEASURES SHOULD BE DOCUMENTED THOROUGHLY.

3. WHERE BMPs HAVE FAILED, REPAIR OR REPLACEMENT SHOULD BE INITIATED UPON DISCOVERY OF THE FAILURE.

4. THE CWA SHALL BE REPAIRED, CLEANED, OR ENLARGED AS NECESSARY TO MAINTAIN CAPACITY FOR CONCRETE WASTE. CONCRETE MATERIALS, ACCUMULATED IN PIT, SHALL BE REMOVED ONCE THE MATERIALS HAVE REACHED A DEPTH OF 2'.

5. CONCRETE WASHOUT WATER, WASTED PIECES OF CONCRETE AND ALL OTHER DEBRIS IN THE SUBSURFACE PIT SHALL BE TRANSPORTED FROM THE JOB SITE IN A WATER-TIGHT CONTAINER AND DISPOSED OF PROPERLY.

6. THE CWA SHALL REMAIN IN PLACE UNTIL ALL CONCRETE FOR THE PROJECT IS PLACED.

7. WHEN THE CWA IS REMOVED, COVER THE DISTURBED AREA WITH TOP SOIL, SEED AND MULCH OR OTHERWISE STABILIZED IN A MANNER APPROVED BY THE LOCAL JURISDICTION.

(DETAIL ADAPTED FROM DOUGLAS COUNTY, COLORADO AND THE CITY OF PARKER, COLORADO, NOT AVAILABLE IN AUTOCAD).


NOTE: MANY JURISDICTIONS HAVE BMP DETAILS THAT VARY FROM UDFCD STANDARD DETAILS. CONSULT WITH LOCAL JURISDICTIONS AS TO WHICH DETAIL SHOULD BE USED WHEN DIFFERENCES ARE NOTED.

 $\underline{\text{NOTE:}}$ MANY JURISDICTIONS HAVE BMP DETAILS THAT VARY FROM UDFCD STANDARD DETAILS. CONSULT WITH LOCAL JURISDICTIONS AS TO WHICH DETAIL SHOULD BE USED WHEN DIFFERENCES ARE NOTED.

Urban Drainage and Flood Control District

Urban Storm Drainage Criteria Manual Volume 3

(DETAILS ADAPTED FROM CITY OF BROOMFIELD, COLORADO, NOT AVAILABLE IN AUTOCAD)



Urban Storm Drainage Criteria Manual Volume 3

Inlet Protection (IP)

SC-6

GENERAL INLET PROTECTION INSTALLATION NOTES

INLET PROTECTION MAINTENANCE NOTES

INSTALL INLET PROTECTION PRIOR TO ONSET OF EVENT.

-TYPE OF INLET PROTECTION (IP.1, IP.2, IP.3, IP.4, IP.5, IP.6)

2. INLET PROTECTION SHALL BE INSTALLED PROMPTLY AFTER INLET CONSTRUCTION OR PAVING IS COMPLETE (TYPICALLY WITHIN 48 HOURS). IF A RAINFALL/RUNOFF EVENT IS FORECAST,

3. MANY JURISDICTIONS HAVE BMP DETAILS THAT VARY FROM UDFCD STANDARD DETAILS. CONSULT WITH LOCAL JURISDICTIONS AS TO WHICH DETAIL SHOULD BE USED WHEN DIFFERENCES ARE NOTED.

1. INSPECT BMPs EACH WORKDAY, AND MAINTAIN THEM IN EFFECTIVE OPERATING CONDITION MAINTENANCE OF BMPs SHOULD BE PROACTIVE, NOT REACTIVE. INSPECT BMPs AS SOON AS POSSIBLE (AND ALWAYS WITHIN 24 HOURS) FOLLOWING A STORM THAT CAUSES SURFACE EROSION, AND PERFORM NECESSARY MAINTENANCE.

2. FREQUENT OBSERVATIONS AND MAINTENANCE ARE NECESSARY TO MAINTAIN BMPs IN EFFECTIVE OPERATING CONDITION. INSPECTIONS AND CORRECTIVE MEASURES SHOULD BE DOCUMENTED THOROUGHLY.

4. SEDIMENT ACCUMULATED UPSTREAM OF INLET PROTECTION SHALL BE REMOVED AS NECESSARY TO MAINTAIN BMP EFFECTIVENESS, TYPICALLY WHEN STORAGE VOLUME REACHES

50% OF CAPACITY, A DEPTH OF 6" WHEN SILT FENCE IS USED, OR 14 OF THE HEIGHT FOR STRAW BALES.

5. INLET PROTECTION IS TO REMAIN IN PLACE UNTIL THE UPSTREAM DISTURBED AREA IS PERMANENTLY STABILIZED, UNLESS THE LOCAL JURISDICTION APPROVES EARLIER REMOVAL OF INLET PROTECTION IN STREETS.

6. WHEN INLET PROTECTION AT AREA INLETS IS REMOVED, THE DISTURBED AREA SHALL BE COVERED WITH TOP SOIL, SEEDED AND MULCHED, OR OTHERWISE STABILIZED IN A MANNER APPROVED BY THE LOCAL JURISDICTION.

(DETAIL ADAPTED FROM TOWN OF PARKER, COLORADO AND CITY OF AURORA, COLORADO, NOT AVAILABLE IN AUTOCAD)

NOTE: MANY JURISDICTIONS HAVE BMP DETAILS THAT VARY FROM UDFCD STANDARD DETAILS. CONSULT WITH LOCAL JURISDICTIONS AS TO WHICH DETAIL SHOULD BE USED WHEN DIFFERENCES ARE NOTED.

NOTE: THE DETAILS INCLUDED WITH THIS FACT SHEET SHOW COMMONLY USED, CONVENTIONAL METHODS OF INLET PROTECTION IN THE DENVER METROPOLITAN AREA. THERE ARE MANY PROPRIETARY INLET PROTECTION METHODS ON THE MARKET. UDFCD NEITHER ENDORSES NOR DISCOURAGES USE OF PROPRIETARY INLET PROTECTION; HOWEVER, IN THE EVENT PROPRIETARY METHODS ARE USED, THE APPROPRIATE DETAIL FROM THE MANUFACTURER MUST

BE INCLUDED IN THE SWMP AND THE BMP MUST BE INSTALLED AND MAINTAINED AS SHOWN IN THE MANUFACTURER'S DETAILS.

NOTE: SOME MUNICIPALITIES DISCOURAGE OR PROHIBIT THE USE OF STRAW BALES FOR INLET PROTECTION. CHECK WITH LOCAL JURISDICTION TO DETERMINE IF STRAW BALE INLET PROTECTION IS ACCEPTABLE.

Urban Drainage and Flood Control District


Urban Storm Drainage Criteria Manual Volume 3

3. WHERE $\mbox{BMP9}$ HAVE FAILED, REPAIR OR REPLACEMENT SHOULD BE INITIATED UPON DISCOVERY OF THE FAILURE.

1. SEE PLAN VIEW FOR:

Inlet Protection (IP)

August 2013



November 2010 Urban Drainage and Flood Control District Urban Storm Drainage Criteria Manual Volume 3

Silt Fence (SF)

SF-3

SILT FENCE INSTALLATION NOTES 1. SILT FENCE MUST BE PLACED AWAY FROM THE TOE OF THE SLOPE TO ALLOW FOR WATER PONDING. SILT FENCE AT THE TOE OF A SLOPE SHOULD BE INSTALLED IN A FLAT LOCATION AT LEAST SEVERAL FEET (2-5 FT) FROM THE TOE OF THE SLOPE TO ALLOW ROOM FOR 2. A UNIFORM 6" X 4" ANCHOR TRENCH SHALL BE EXCAVATED USING TRENCHER OR SILT FENCE INSTALLATION DEVICE. NO ROAD GRADERS, BACKHOES, OR SIMILAR EQUIPMENT SHALL BE USED. 3. COMPACT ANCHOR TRENCH BY HAND WITH A "JUMPING JACK" OR BY WHEEL ROLLING. COMPACTION SHALL BE SUCH THAT SILT FENCE RESISTS BEING PULLED OUT OF ANCHOR TRENCH BY HAND. 4. SILT FENCE SHALL BE PULLED TIGHT AS IT IS ANCHORED TO THE STAKES. THERE SHOULD BE NO NOTICEABLE SAG BETWEEN STAKES AFTER IT HAS BEEN ANCHORED TO THE STAKES. 5. SILT FENCE FABRIC SHALL BE ANCHORED TO THE STAKES USING 1" HEAVY DUTY STAPLES OR NAILS WITH 1" HEADS. STAPLES AND NAILS SHOULD BE PLACED 3" ALONG THE FABRIC 6. AT THE END OF A RUN OF SILT FENCE ALONG A CONTOUR, THE SILT FENCE SHOULD BE TURNED PERPENDICULAR TO THE CONTOUR TO CREATE A "J-HOOK." THE "J-HOOK" EXTENDING PERPENDICULAR TO THE CONTOUR SHOULD BE OF SUFFICIENT LENGTH TO KEEP RUNOFF FROM FLOWING AROUND THE END OF THE SILT FENCE (TYPICALLY 10' - 20'). 7. SILT FENCE SHALL BE INSTALLED PRIOR TO ANY LAND DISTURBING ACTIVITIES. SILT FENCE MAINTENANCE NOTES 1. INSPECT BMPs EACH WORKDAY, AND MAINTAIN THEM IN EFFECTIVE OPERATING CONDITION. MAINTENANCE OF BMPs SHOULD BE PROACTIVE, NOT REACTIVE. INSPECT BMPs AS SOON AS POSSIBLE (AND ALWAYS WITHIN 24 HOURS) FOLLOWING A STORM THAT CAUSES SURFACE EROSION, AND PERFORM NECESSARY MAINTENANCE. 3. WHERE BMPs HAVE FAILED, REPAIR OR REPLACEMENT SHOULD BE INITIATED UPON DISCOVERY OF THE FAILURE. 4. SEDIMENT ACCUMULATED UPSTREAM OF THE SILT FENCE SHALL BE REMOVED AS NEEDED TO MAINTAIN THE FUNCTIONALITY OF THE BMP, TYPICALLY WHEN DEPTH OF ACCUMULATED SEDIMENTS IS APPROXIMATELY 6". 5. REPAIR OR REPLACE SILT FENCE WHEN THERE ARE SIGNS OF WEAR, SUCH AS SAGGING, 6. SILT FENCE IS TO REMAIN IN PLACE UNTIL THE UPSTREAM DISTURBED AREA IS STABILIZED AND APPROVED BY THE LOCAL JURISDICTION, OR IS REPLACED BY AN EQUIVALENT PERIMETER SEDIMENT CONTROL BMP. 7. WHEN SILT FENCE IS REMOVED, ALL DISTURBED AREAS SHALL BE COVERED WITH TOPSOIL SEEDED AND MULCHED OR OTHERWISE STABILIZED AS APPROVED BY LOCAL JURISDICTION. (DETAIL ADAPTED FROM TOWN OF PARKER, COLORADO AND CITY OF AURORA, NOT AVAILABLE IN AUTOCAD) $\underline{\text{NOTE:}}$ many jurisdictions have BMP details that vary from udfcd standard details. Consult with local jurisdictions as to which detail should be used when differences are noted.

Urban Drainage and Flood Control District

Urban Storm Drainage Criteria Manual Volume 3

-Compost filter sock size varies. See Plans and notes. Compost Filter Sock Drainage grate Wire tied (Typ) Secure with zip-tie when staking is not feasible or desired DROP INLET PLAN N.T.S. Inside diameter 2"x2" x 3'-0" wooden stakes 3' O.C. (Typ when conditions allow. Tie sock at overlap to prevent sock movement when not staked (pavement application). DROP INLET PERSPECTIVE VIEW N.T.S.

-Place a sandbaa at

CURB INLET PERSPECTIVE VIEW

N.T.S.

hold in place.

PLACE RIP-RAP IN ALL AREAS INDICATED ON THE DRAWING. THE STONE SHALL CONSIST OF FIELD STONE OR ROUGH, UNHEWN QUARRY STONE AS NEARLY UNIFORM IN SECTION AS IS PRACTICAL. THI STONES SHALL BE DENSE, RESISTANT TO THE ACTION OF AIR AND WATER, AND SUITABLE IN ALL ASPECTS FOR THE PURPOSE INTENDED, UNLESS OTHERWISE SPECIFIED, ALL STONES USED AS RIP-RAP SHALL WEIGH BETWEEN 50-150 POUNDS EACH, AND AT LEAST 60 PERCENT OF THE STONES SHALL WEIGH MORE THAN 100 POUNDS EACH. SEE PLAN FOR SIZE RIP-RAP PAD FOR SLOPE PROTECTION

> COMPOST FILTER MEDIA SPECIFICATIONS . ANCHORING STAKES SHALL BE SIZED, SPACED, AND BE OF A MATERIAL THAT

2. OVERLAP ENDS OF SOCK PER MANUFACTURERS RECOMMENDATIONS. (1' MIN. 3' 3. USE 8" TO 12" DIA. SOCK ON CURBSIDE IN TRAFFIC AREAS.

EFFECTIVELY SECURES THE FILTER SOCK. STAKE SPACING SHALL BE A MAXIMUM OF THREE FEET.

4. USE 12" - 18" DIA. SOCK IN NON-TRAFFIC AREAS OR AREAS WHERE SAFETY DESIGN CRITERIA:

COMPOST FILTER SOCKS ARE DESIGNED TO RETAIN SEDIMENT TRANSPORTED IN SHEET FLOW FROM DISTURBED AREAS. COMPOST FILTER SOCKS PERFORM THE SAME FUNCTION AS SILT FENCE, ALLOW A HIGHER FLOW RATE, AND ARE USUALLY FASTER AND CHEAPER TO INSTALL. WHERE ALL RUNOFF IS TO BE TREATED BY THE COMPOST FILTER SOCK THE MAXIMUM SLOPE LENGTH BEHIND THE COMPOST FILTER SOCK SHAL OT EXCEED THOSE SHOWN IN TABLE 1. THE DRAINAGE AREA SHALL NOT EXCEED 1/4 ACRE FOR EVERY 100 FT OF COMPOST FILTER SOCK.

THE SEDIMENT AND POLLUTANT REMOVAL PROCESS CHARACTERISTIC TO COMPOST FILTER SOCKS COMBINES BOTH FILTERING AND DEPOSITION FROM SETTLING SOLIDS THIS IS DIFFERENT THAN METHODS THAT RELY ON PONDING FOR DEPOSITION OF SOLIDS FOR SEDIMENT CONTROL. SUCH AS SILT FENCE. PONDING OCCURS WHEN WATER FLOWING TO THE COMPOST FILTER SOCK ACCUMULATES FASTER THAN THE HYDRAULIC FLOW THROUGH RATE OF THE COMPOST FILTER SOCK. HYDRAULI FLOW-THROUGH RATES FOR COMPOST FILTER SOCKS. ARE 50% GREATER THAN SILT FENCE FILTER FABRIC. GREATER HYDRAULIC FLOW-THROUGH RATES REDUCE PONDING COMPOST FILTER SOCK MESH NETTING SHALL MEET THE NETTING SPECIFICATION I TABLE 2. COMPOST FILTER SOCKS SHALL MEET THE SPECIFICATIONS IN TABLE 3. COMPOST USED IN COMPOST FILTER SOCKS SHALL MEET THE SPECIFICATION DESCRIBED UNDER COMPOST FILTER MEDIA SPECIFICATIONS.

A 12 INCH DIAMETER COMPOST FILTER SOCK SHALL BE USED ON DEVELOPMENTS WHERE THE LIFE OF THE PROJECT IS GREATER THAN OR EQUAL TO SIX MONTHS. A 12 INCH DIAMETER COMPOST FILTER SOCK MAY ALSO BE USED ON MINOR PROJECTS, SUCH AS RESIDENTIAL HOME SITES OR SMALL COMMERCIAL DEVELOPMENTS.

Maximum Slope Length Above Compost Filter Sock
Feet
100
75
50
25
15
_

	TABLE 2	
Material Type	Multi-Filament Polypropylene	Multi-Filament Polypropylene
Material Characteristic	Photodegradable	Photodegradable
Mesh Opening	3/8 in (10mm)	1/8 in (3mm)
"Tensile Strength (ASTM 5035-95)"	44 psi (3.09 kg/cm2)	202 psi (14.2 kg/cm2)*
% Original Strength from Ultraviolet Exposure (ASTM G-155)	100% at 1000 hr	100% at 1000 hr

TABLE 3 fective Circumference 38 in (960mm) Density (when filled) 32 lbs/ft (50 kg/m) Hydraulic Flow Through Rate 11.3 gpm/ft (141 P Factor (RUSLE) 0.1-0.32

COMPOST USED FOR COMPOST FILTER SOCK FILLER MATERIAL (FILTER MEDIA) SHALL BE WEED FREE AND DERIVED FROM A WELL—DECOMPOSED SOURCE OF ORGANIC MATTER. THE COMPOST SHALL BE PRODUCED USING AN AEROBIC COMPOSTING PROCESS MEETING CFR 503 REGULATIONS INCLUDING TIME AND TEMPERATURE DATA. THE COMPOST SHALL BE FREE OF ANY REFUSE, CONTAINING PROCESS MEETING CONTAINING PROCESSES.

CONTAMINANTS OR OTHER MATERIALS TOXIC TO PLANT GROWTH. NON-COMPOSTED PRODUCTS WILL NOT BE ACCEPTED. TEST METHODS FOR THE ITEMS BELOW SHOULD FOLLOW US COMPOSTING COUNCIL TEST METHODS FOR THE EXAMINATION OF

A. PH - 5.0-8.0 IN ACCORDANCE WITH TMECC 04.11-A, "ELECTROMETRIC PH DETERMINATIONS FOR COMPOST"

B. PARTICLE SIZE -99% PASSING A 2 IN (50MM) SIEVE AND A MAXIMUM OF 40% PASSING A 3/8 IN (9.5MM) SIEVE, IN ACCORDANCE WITH TMECC 02.02-B,

"SAMPLE SIEVING FOR AGGREGATE SIZE CLASSIFICATION". (NOTE- IN THE FIELD. PRODUCT COMMONLY IS BETWEEN 1/2 IN [12.5MM] AND 2 IN [50MM] PARTICLE

C. MOISTURE CONTENT OF LESS THAN 60% IN ACCORDANCE WITH STANDARDIZED TEST METHODS FOR MOISTURE DETERMINATION.

D. MATERIAL SHALL BE RELATIVELY FREE (<1% BY DRY WEIGHT) OF INERT OR

E. A SAMPLE SHALL BE SUBMITTED TO THE ENGINEER FOR APPROVAL PRIOR TO

THE COMPOST FILTER SOCK SHALL BE INSTALLED ACCORDING TO THIS SPECIFICATION, AS SHOWN ON THE PLANS OR AS DIRECTED BY THE ENGINEER.

1. COMPOST FILTER SOCKS SHOULD BE INSTALLED PARALLEL TO THE BASE OF THE

2. STAKES SHALL BE INSTALLED THROUGH THE MIDDLE OF THE COMPOST FILTER SOCK ON 10 FT (3M) CENTERS, USING 2 IN (50MM) BY 2 IN (50MM) BY 3 FT

3. STAKING DEPTH FOR SAND AND SILT LOAM SOILS SHALL BE 12 IN (300MM), AND

4. LOOSE COMPOST MAY BE BACKFILLED ALONG THE UPSLOPE SIDE OF THE COMPOST FILTER SOCK, FILLING THE SEAM BETWEEN THE SOIL SURFACE AND THE

5. IF THE COMPOST FILTER SOCK IS TO BE LEFT AS A PERMANENT FILTER OR PART

6. COMPOST FILTER SOCKS ARE NOT TO BE USED IN PERENNIAL, EPHEMERAL, OR

SEDIMENT SHALL BE REMOVED ONCE IT HAS ACCUMULATED TO ONE—HALF THE ORIGINAL HEIGHT OF THE BARRIER. COMPOST FILTER SOCKS SHALL BE REPLACED WHENEVER IT HAS DETERIORATED TO SUCH AN EXTENT THAT THE EFFECTIVENESS OF COMPOST FILTER SOCK IS REDUCED. COMPOST FILTER SOCKS SHALL REMAIN IN

PLACE UNTIL DISTURBED AREAS HAVE BEEN PERMANENTLY STABILIZED. ALL SEDIMENT ACCUMULATION AT THE COMPOST FILTER SOCK SHALL BE REMOVED AND PROPERLY DISPOSED OF BEFORE THE COMPOST FILTER SOCK IS REMOVED.

OF THE NATURAL LANDSCAPE, IT MAY BE SEEDED AT TIME OF INSTALLATION FOR ESTABLISHMENT OF PERMANENT VEGETATION. THE ENGINEER WILL SPECIFY SEED

DEVICE, IMPROVING FILTRATION AND SEDIMENT RETENTION.

SLOPE OR OTHER DISTURBED AREA. IN EXTREME CONDITIONS (I.E., 2:1 SLOPES), A SECOND COMPOST FILTER SOCK SHALL BE CONSTRUCTED AT THE TOP OF THE

(1M) WOODEN STAKES. IN THE EVENT STAKING IS NOT POSSIBLE, I.E., WHEN COMPOST FILTER SOCKS ARE USED ON PAVEMENT, HEAVY CONCRETE BLOCKS

SHALL BE USED BEHIND THE COMPOST FILTER SOCKS TO HELP STABILIZE DURING

BEING USED AND MUST COMPLY WITH ALL LOCAL, STATE AND FEDERAL REGULATIONS.

COMPOSTING AND COMPOST GUIDELINES FOR LABORATORY PROCEDURES:

FOREIGN MAN MADE MATERIALS.

CONSTRUCTION SPECIFICATIONS

RAINFALL/RUNOFF EVENTS.

8 IN (200MM) FOR CLAY SOILS.

INTERMITTENT STREAMS.

<u>MAINTENANCE</u>

PROFESSIONAL IN CHARGE FARMAN SHIR, PE PROFESSIONAL ENGINEER LICENSE NO. 21307

> PROJECT MANAGER MARLEY PHILLIPS **QUALITY CONTROL** KIEW KAM, PE

NICOLE NOVACK **PROJECT NAME**

DRAWN BY

CIRCLE K

SAN JUAN COUNTY NEW MEXICO 819 NM 516

FLORA VISTA



PROJECT NUMBER

SHEET TITLE

EROSION CONTROL DETAILS

SHEET NUMBER

COMPOST FILTER SOCK

19000 MacArthur BlvD. Suite 250 Irvine, CA 92612 t: 949 296 0450 f: 949 296 0479

PROJECT TEAM

COPYRIGHT NOTICE

This drawing is the property of the above

referenced Professional and is not to be used

for any purpose other than the specific

project and site named herein, and cannot

be reproduced in any manner without the


express written permission from the Profe


ISSUE/REVISION RECORD

DESCRIPTION

08-07-14 DEVELOPMENT PLAN

PROFESSIONAL SEAL





EXISTING LEGEND:

L			
O-PIPELINE VENT	P -TELE. PED.	□ −TRAFFIC CONTROL BOX □ −ROAD SIGN	LIST OF ABBREVIATIONS U/G - UNDERGROUND
GAS METER	P -ELEC. PEDESTAL	1	HC — HANDICAPPED CONC. — CONCRETE
ZZ −SIGNAL LIGHT	-WATER VALVE	-GROUND LIGHT	RET. — RETAINING APPROX. — APPROXIMATE SAN. — SANITARY
₹	-POWER POLE	- UTILITY POLE	ASPH. – ASPHALT TYP. – TYPICAL
-MAIL BOX		O -GAS VALVE	BLDG. — BUILDING PED. — PEDESTAL PLTR. — PLANTER
⊕ –BUSH	-FIRE HYDRANT .H.	◯ – TEL. U.G. MRKR.	G/R - GAS REGULATOR
_	7	T-TELE. MANHOLE	G/L — GROUND LIGHT TRANS — TRANSFORMER
W/ M.H. COVER	+ - TREE	E-ELEC. MANHOLE	F.F FINISHED FLOOR
(SS) -SAN. SEW. M.H.	S -STM. SEW. M.H.	-STOCKADE FCE	C - CENTER LINE R.O.W - RIGHT-OF-WAY
-GUY WIRE	GP-GUARD POST	X-BARB WIRE FCE	FCE. — FENCE BIA. — DIAMETER
C -CLEAN OUT		CHAIN LINK FCE	BLVD. – BOULEVARD B/L – BUILDING SETBACK LINE
	△ MONITOR WEL	L TC WATER METER	ESMT EASEMENT A/S - AUTO-SPRINKLER
_	—STS	🗌 – TRASH CAN	DIST DISTANCE
ET - ELEC TRANS	STORM SEWER	—— ss——	BRNG BEARING
 F/0 	UNDERGROUND	SANITARY SEWER	W/UGS - WITH UNDERGROUND SERVICE
FIBER OPTIC UTA	COMMUNICATION	WATER LINE	MW - MONITOR WELL
₩ – UNDERGROUND	TANK ACCESS	-HANDICAP	STAT STATUTORY M - MEASURED
-CONCRETE	W.H.	T	DIMENSION P — PLAT DIMENSION IG — IRON GRATE
-TRAFFIC DIRE	CTION	FR -FIRE RISER	R - RECORD DIMENSION RD - ROOF DRAIN
TR - TOP OF RIM		AUTO SPRINKLER	P.O.M POINT OF

GENERAL UTILITY NOTES:

FL - FLOW LINE

1. CONTRACTOR IS TO VERIFY THE LOCATION OF ALL EXISTING UTILITIES PRIOR TO CONSTRUCTION AND ENSURE NO CONFLICTS EXIST WITH PROPOSED IMPROVEMENTS. NOTIFY ENGINEER IMMEDIATELY IF UTILITIES ARE LOCATED DIFFERENTLY THAN SHOWN. THE CONTRACTOR SHALL COORDINATE WITH EACH RESPECTIVE UTILITY COMPANY IN ORDER TO RELOCATE IF NEEDED IN CONFORMANCE WITH THEIR GUIDELINES.

2. CONTRACTOR SHALL NOTIFY AND COORDINATE WITH THE APPROPRIATE UTILITY COMPANY PRIOR TO THE REMOVAL OF INDICATED UTILITIES ON SITE (SEE DEMOLITION PLAN). CONTRACTOR SHALL BE RESPONSIBLE FOR OBTAINING ANY PERMITS REQUIRED FOR DEMOLITION AND HAUL OFF FROM THE APPROPRIATE AUTHORITIES.

3. AUTHORIZATION MUST BE OBTAINED FROM THE NEW MEXICO ENVIRONMENT DEPARTMENT AND FLORA VISTA MUTUAL DOMESTIC WATER TO CONSTRUCT, ALTER OR MODIFY A WATER OR SEWER LINE. CONSTRUCTION OF WATER AND SEWER INFRASTRUCTURE WILL BE AUTHORIZED BY THE WATER SYSTEM UPON:

APPROVAL OF SUBMITTED PLANS.
 NOTIFICATION OF THE WATER SYSTEM AT LEAST 24

HOURS PRIOR TO STARTING CONSTRUCTION.

4. AT THE COMPLETION OF THE WATER AND/OR SEWER CONSTRUCTION

AND PRIOR TO RECORDING THE FINAL PLAT, THE CONTRACTOR WILL FURNISH THE WATER SYSTEM INSPECTOR RECORD DRAWINGS OF THE PROJECT.

5. BUILDING CONTRACTOR SHALL BE RESPONSIBLE FOR COORDINATION

WITH THE GAS COMPANY FOR THE CONSTRUCTION OF THE GAS LINE BETWEEN METER AND MAIN.

6. BUILDING CONTRACTOR SHALL BE RESPONSIBLE FOR COORDINATION

WITH THE POWER COMPANY FOR THE CONSTRUCTION OF ELECTRICAL CONDUIT TO PROVIDE SERVICE TO THE TRANSFORMER.

7. THE CONTRACTOR SHALL BE RESPONSIBLE FOR VERIFYING, PRIOR TO CONSTRUCTION, ALL EXISTING LOCATIONS AND INVERT ELEVATIONS OF SANITARY SEWERS, STORM DRAINAGE, AND WATER MAINS. IF ANY INVERT ELEVATION VARIES MORE THAN 0.1 FT. FROM RECORD ELEVATIONS, THE CONTRACTOR SHALL NOTIFY THE ENGINEER IMMEDIATELY. WORK SHALL NOT PROCEED UNTIL THE CONTRACTOR IS NOTIFIED BY THE ENGINEER.

8. CONNECT TO EXISTING UTILITIES AND INSTALL UTILITIES IN COMPLIANCE WITH REQUIREMENTS OF APPROPRIATE JURISDICTIONAL AGENCIES.

9. COORDINATE WITH BUILDING PLANS TO ASSURE ACCURACY OF UTILITY CONNECTIONS AND COMPLIANCE WITH LOCAL CODES.

10. ALL SEWERS TO BE MAINTAINED THROUGHOUT CONSTRUCTION, INCLUDING CLEANING OF ANY SILT OR DEBRIS ACCUMULATED IN STRUCTURES.

11. ALL SURPLUS EXCAVATED MATERIAL FROM THE TRENCH SHALL BE

DISPOSED OFF THE SITE BY CONTRACTOR.

12. COORDINATE EXACT TRENCHING, ROUTING, AND POINT OF TERMINATION

WITH ALL UTILITY COMPANIES.

13. ALL WATER LINES SHALL HAVE AT LEAST FOUR AND ONE HALF (4.5)

FEET GROUND COVER FROM THE TOP OF THE PIPE TO THE FINISHED GROUND SURFACE.

14. ALL WATER LINES 2" OR SMALLER SHALL BE TYPE K-COPPER.

15. THE CONTRACTOR IS RESPONSIBLE FOR OBTAINING UTILITY LOCATES.

GreenbergFarrow

5500 Democracy Dr. Suite 125

PROJECT TEAM

Plano, TX 75024 t: 972 514 7641

COPYRIGHT NOTICE

This drawing is the property of the above referenced Professional and is not to be used for any purpose other than the specific project and site named herein, and cannot be reproduced in any manner without the express written permission from the Professional

ISSUE/REVISION RECORD

DATE DESCRIPTION

08-07-14 DEVELOPMENT PLAN

PROFESSIONAL IN CHARGE FARMAN SHIR, PE

LICENSE NO. 21307

PROJECT MANAGER

MARLEY PHILLIPS

QUALITY CONTROL

KIEW KAM, PE

DRAWN BY

PROFESSIONAL ENGINEER

PROJECT NAME

NICOLE NOVACK

CIRCLE K

SAN JUAN COUNTY NEW MEXICO


819 NM 516 FLORA VISTA



PROJECT NUMBER

SHEET TITLE

UTILITY PLAN



N.T.S.

GreenbergFarrow

5500 Democracy Dr. Suite 125 Plano, TX 75024

PROJECT TEAM

COPYRIGHT NOTICE This drawing is the property of the above referenced Professional and is not to be used for any purpose other than the specific project and site named herein, and cannot be reproduced in any manner without the

ISSUE/REVISION RECORD

DESCRIPTION 08-07-14 DEVELOPMENT PLAN

PROFESSIONAL IN CHARGE FARMAN SHIR, PE

LICENSE NO. 21307 PROJECT MANAGER MARLEY PHILLIPS **QUALITY CONTROL**

NICOLE NOVACK

CIRCLE K


SAN JUAN COUNTY NEW MEXICO 819 NM 516





PROJECT NUMBER


SHEET TITLE


DETAIL SHEET











5500 Democracy Dr. Suite 125 Plano, TX 75024 t: 972 514 7641

PROJECT TEAM

COPYRIGHT NOTICE This drawing is the property of the above referenced Professional and is not to be used for any purpose other than the specific project and site named herein, and cannot be reproduced in any manner without the

ISSUE/REVISION RECORD

08-07-14 DEVELOPMENT PLAN

DATE DESCRIPTION

PROFESSIONAL IN CHARGE FARMAN SHIR, PE PROFESSIONAL ENGINEER LICENSE NO. 21307

PROJECT MANAGER MARLEY PHILLIPS **QUALITY CONTROL** KIEW KAM, PE

PROJECT NAME

DRAWN BY

NICOLE NOVACK

CIRCLE K

SAN JUAN COUNTY NEW MEXICO 819 NM 516


FLORA VISTA





PROJECT NUMBER


SHEET TITLE

DETAIL SHEET









reenbergFarrow

5500 Democracy Dr. Suite 125 Plano, TX 75024 t: 972 514 7641

PROJECT TEAM

COPYRIGHT NOTICE
This drawing is the property of the above referenced Professional and is not to be used for any purpose other than the specific project and site named herein, and cannot be reproduced in any manner without the express written permission from the Professional

ISSUE/REVISION RECORD

DATE DESCRIPTION
08-07-14 DEVELOPMENT PLAN

PROFESSIONAL IN CHARGE FARMAN SHIR, PE PROFESSIONAL ENGINEER

LICENSE NO. 21307

PROJECT MANAGER
MARLEY PHILLIPS

QUALITY CONTROL

KIEW KAM, PE

DRAWN BY

NICOLE NOVACK

PROJECT NAME

CIRCLE K

SAN JUAN COUNTY NEW MEXICO

819 NM 516 Flora Vista



PROJECT NUMBER

SHEET TITLE

DETAIL SHEET

C-7 2